



December 4, 2022

City of Cuba
Po Box
Cuba, Mo 65435
Quote # 1242301

Well, XFMR Addition and Controls:

A. Well, XFMR to Include the Following:

- Installation of Fused Disconnect
- Installation of Transformer 45KVA Primary 480, Secondary 240
- Proper Bonding of transformer
- Removal of existing single-Phase Service "working with Power company"
- Install New Feeder top Existing Panel
- Install New Precision Digital PLC in Existing SCADA Panel
- Installation of Proper Control Wiring Redundant Back up
- Install New S811 Soft Start and Power Supply
- Install New Distribution Block and Well Breaker
- Install New Phase Monitor
- Clean up all Control wiring in control panel
- Supply & Install all Materials Listed Above
- Start Up and Testing

Quote Total \$22,652.00

Accepted By _____

Company _____

Date _____


Firm thirty (30) days from bid date

- Net 30 days with 1 1/2% per month add
- Without any applicable taxes


Steve Durbin
Aesthetix Electric

THANK YOU FOR YOUR BUSINESS AND REFERRALS!

573.348.1429
aesthetixelectric.com | steve@aesthetixelectric.com
PO Box 972 | Osage Beach MO, 65065



ECCO ELECTRIC COMPANY



8/3/2022

City of Cuba
P.O. Box K
Cuba, MO 65453

Attn: Glen

Ref: Well 4 Controls and Transformer

Quote #2265032522

We are pleased to offer the following for your consideration:

A Well #4 control panel to include

- N-1 enclosure
- Distribution block
- Transient voltage surge suppressor
- 150-amp pump breaker
- 25-amp transformer breaker
- New s811 starter (135 amp)
- Power supply
- Pressure controller
- 10 KVA transformer
- SCADA interface
- Pump to waste interface
- Start up and test

B. Installation to include:

- Remove existing controls
- Re-route existing conduits
- Mount new transformer
- New conduit and wire for transformer

Items NOT included: 1) Disposal of existing equipment
2) Pressure taps and piping

TOTAL PRICE \$ 30,947.00

ELECTRICAL CONTRACTING AND CONTROLS